BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT51697

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/03/2022-23, Date: 21-05-2022

Name of Work:Improvements to Roads and Drains at Virupakshapura, Budha Jyothi Layout, Kodigehalli, Maruthi Layout and Surrounding areas in Ward No. 09 (Vidyaranyapura).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SHANKARREDDY KALLEPALLI ( )	
				In Figures	In Words
1	17.35	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead I By Manual Means B Cement Concrete and as per the directions of the Engineer-in-charge of the work .	Cum	820.18	Rupees Eight Hundred Twenty and Eighteen Paise Only
2	22.63	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead (iii) Dismantling Stone Masonry B Rubble stone masonry in cement mortar.and as per the directions of the Engineer-in-charge of the work .	Cum	539.68	Rupees Five Hundred Thirty Nine and Sixty Eight Paise Only
3	2437.16	Removing and refixing stone slabs of drains and pointing in CM (1:3) and as per the directions of the Engineer-in-charge of the work .	Sqm	113.53	Rupees One Hundred Thirteen and Fifty Two Paise Only
4	2517.44	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. and as per the directions of the Engineer-in-charge of the work .	Cum	208.69	Rupees Two Hundred Eight and Sixty Nine Paise Only
5	1044.50	Providing granite slabs of selected quality roughly dressed having a size of 7.5cms thick and fixed in cement mortar (1:6) including fixing curing ete., completeand as per the directions of the Engineer-in-charge of the work .	Sqm	756.84	Rupees Seven Hundred Fifty Six and Eighty Four Paise Only
6	1023.23	Providing granite slabs of selected quality roughly dressed havinf a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete.and as per the directions of the Engineer-in-charge of the work .	Sqm	986.05	Rupees Nine Hundred Eighty Six and Five Paise Only
7	261.50	Providing and laying in position plain cement concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. and as per the directions of the Engineer-in-charge of the work .	Cum	6453.74	Rupees Six Thousand Four Hundred Fifty Three and Seventy Four Paise Only
8	580.56	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 and as per the directions of the Engineer-in-charge of the work .	Cum	7370.19	Rupees Seven Thousand Three Hundred Seventy and Nineteen Paise Only
9	35.90	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications. and as per the directions of the Engineer-in-charge of the work .	tonne	115935.14	Rupees One Hundred Fifteen Thousand Nine Hundred Thirty Five and Thirteen Paise Only

K. Sankar Reddy
Signature of Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Ra SHANKARREDDY KALLEPALLI ( )	
				In Figures	In Words
10	2631.37	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of all materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. and as per the directions of the Engineer-in-charge of the work .	Sqm	2383.74	Rupees Two Thousand Three Hundred Eighty Three and Seventy Four Paise Only
11	88.68	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.and as per the directions of the Engineer-in-charge of the work .	Sqm	5526.36	Rupees Five Thousand Five Hundred Twenty Six and Thirty Six Paise Only
12	232.39	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. and as per the directions of the Engineer-in-charge of the work .	Cum	6839.71	Rupees Six Thousand Eight Hundred Thirty Nine and Seventy One Paise Only
13	2714.40	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications. and as per the directions of the Engineer-in-charge of the work .	Sqm	1197.17	Rupees One Thousand One Hundred Ninety Seven and Seventeen Paise Only
14	415.00	Supplying and fixing M15 grade precast cement concrete 600 x 300 x 150 mm Kerb Stone for Roadway, Sidewalls and gutters fixed with CM 1:3 fixed and finsihed in line as per direction of Engineer in charge. and as per the directions of the Engineer-in-charge of the work .	m	474.61	Rupees Four Hundred Seventy Four and Sixty Paise Only
15	145.25	Painting Two Coats on New Concrete Surfaces Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concretesurfaces. and as per the directions of the Engineer-in-charge of the work .	Sqm	95.37	Rupees Ninety Five and Thirty Seven Paise Only
16	405.42	Earth work in surface excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work. In all kinds of soils upto 300 mm depth. and as per the directions of the Engineer-in-charge of the work .	Cum	72.93	Rupees Seventy Two and Ninety Three Paise Only
17	7106.32	Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material by Mechanical Means using Hydraulic excavator with in all lifts and lead MORTH Specification and as per the directions of the Engineer-in-charge of the work .	Sqm	4.49	Rupees Four and Forty Eight Paise Only
18	7281.32	Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications. and as per the directions of the Engineer-in-charge of the work .	Sqm	6.49	Rupees Six and Forty Eight Paise Only
19	26.25	Construction of Granular Sub-Base of required grading as per design mixing in a mechanical mix plant at OMC, carriageof mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, and as per the directions of the Engineer-in-charge of the work .	Cum	2633.33	Rupees Two Thousand Six Hundred Thirty Three and Thirty Three Paise Only
20	1980.35	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density and as per the directions of the Engineer-in-charge of the work .	Cum	2686.07	Rupees Two Thousand Six Hundred Eighty Six and Six Paise Only
21	8610.20	Cleaning the existing WBM Road surface including removing of binding materials and other foreign matter with wire brushes and small picks sweeping with brooms or soft brushes and finally dusting with old gunny bags and bar or compressed air to receive bituminous treatment including cost of all materials, labhour, HOM of machineries complet and as per the directions of the Engineer-in-charge of the work .	Sqm	22.71	Rupees Twenty Two and Seventy Paise Only

Signature of Contractor K. Sankar Reddy

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SHANKARREDDY KALLEPALLI ( )	
				In Figures	In Words
22	9036.65	Providing and applying primer coat with SS1 grade Bitumen Emulsion on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.90 kg per m2 using mechanical means and as per the directions of the Engineer-in-charge of the work .	Sqm	49.37	Rupees Forty Nine and Thirty Six Paise Only
23	451.83	Providing and laying Dense Graded Bituminous Macadam with 40/60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per and as per the directions of the Engineer-in-charge of the work .	Cum	11095.46	Rupees Eleven Thousand Ninety Five and Forty Five Paise Only
24	9413.57	Cleaning the existing black topped surface with brooms,soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials,labhour, HOM of machineries complete as per specifications.and as per the directions of the Engineer-in-charge of the work .	Sqm	5.41	Rupees Five and Forty Paise Only
25	9413.57	Providing and applying tack coat with RS1 Bituminous Emulsion using emulsion pressure distributor at the rate of 0.25 kg/m2 on the prepared bituminous surface cleaned with mechanical broom MORTH Specification and as per the directions of the Engineer-in-charge of the work .	Sqm	16.83	Rupees Sixteen and Eighty Three Paise Only
26	376.54	Providing and laying Bituminous Concrete with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 percent of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade,level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification and as per the directions of the Engineer-in-charge of the work .	Cum	12937.78	Rupees Twelve Thousand Nine Hundred Thirty Seven and Seventy Eight Paise Only
27	390.30	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 g/ m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level, uniform and free from streaks and holes. and as per the directions of the Engineer-in-charge of the work .	Sqm	536.32	Rupees Five Hundred Thirty Six and Thirty One Paise Only
28	66.56	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separatelyand as per the directions of the Engineer-in-charge of the work .	Cum	473.48	Rupees Four Hundred Seventy Three and Forty Eight Paise Only
29	49.92	Construction of dry lean cement concrete Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm,aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ m3 , optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 t vibratory roller, finishing and curing. and as per the directions of the Engineer-in-charge of the work .	Cum	4707.91	Rupees Four Thousand Seven Hundred Seven and Ninety One Paise Only
30	49.92	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete MORTH Specification No.1501 . as per the directions of the Engineer-in-charge of the work. (PWD SR 2021-22 Vol -III Pg 138 item no 20.29)	Cum	7671.11	Rupees Seven Thousand Six Hundred Seventy One and Eleven Paise Only

K. Sankar Reddy
Signature of Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender R SHANKARRED KALLEPALLI ( )	
				In Figures	In Words
31	86.40	Cutting transverse contraction joints 3 to 4 mm wide and depth 60mm in concrete slab using concrete cutting machine with diamond studded saw within 48 hours of casting of bay / slab etc. complete including subsequent widening of the groove 8 to 10 mm. wide at top having depth of 15 mm. as directed by Engineer incharge. and as per the directions of the Engineer-in-charge of the work .	m	78.54	Rupees Seventy Eight and Fifty Four Paise Only
32	86.40	Providing to contraction joints polysuphide sealent (Pouring grade) confirming to BS : 5212 - 1989 into sawed groove widened at top for sealent reservoir of specified size and shape as per detailed drawing including fixing Polyethylene foam backer rod of required diameter (approx. 25% larger than the initial 3 mm.to 4 mm. joint) overlaid with bond breaking tape as per detailed drawing. Item includes cleaning the joints with water jet / air compressor and allowing joint to become thoroughly dry before sealent is applied and applying primer. (A) Contraction and longitudinal joints (15 mm. deep x 8mm.wide). and as per the directions of the Engineer-in-charge of the work .	m	185.13	Rupees One Hundred Eighty Five and Thirteen Paise Only
33	3029.41	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. and as per the directions of the Engineer-in-charge of the work .	Cum	83.03	Rupees Eighty Three and Two Paise Only
34	3877.65	Cost of Haulage Excluding Loading and Unloading Taking output 18 t load and lead 10 km = 180 t.km and as per the directions of the Engineer-in-charge of the work .	t.Km	117.81	Rupees One Hundred Seventeen and Eighty One Paise Only

K. Sankar Reddy
Signature of the Contractor

29/7
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
29/7